Bright Spark Electric

(512) 555-9999 • info@brightspark.com
555 Power Lane, Austin, TX 78701 • Lic# ELC-TX-78901

Electrical Panel Upgrade & Kitchen/Bathroom Outlet Installation

CLIENT:
Jennifer Martinez

DATE:
March 23, 2026

VALID UNTIL:
April 6, 2026

CLIENT

Jennifer Martinez
321 Elm Street, Austin, TX 78702
(512) 555-8888
jmartinez@email.com

JOB SITE

321 Elm Street, Austin TX
1970s home with original 100-amp service, needs upgrade to 200-amp for modern appliances

PROJECT

Complete electrical panel upgrade and outlet installation, Start: April 8, 2026, Duration: 1 day, Permit: Included

EXECUTIVE SUMMARY

Bright Spark Electric is pleased to provide this proposal for upgrading your home's electrical service from 100-amp to 200-amp capacity. Your current service is insufficient for modern appliances and creates a fire hazard. We will install a new main panel, upgrade all circuits, and add GFCI-protected outlets throughout your kitchen and bathrooms.

SCOPE OF WORK

- Obtain electrical permit from City of Austin
- Upgrade main service entrance from 100-amp to 200-amp capacity
- Install new 200-amp main breaker panel with 40 available circuit positions
- Install new 200-amp meter base and connect to utility company
- Disconnect and remove old 100-amp panel safely
- Install 8 new 20-amp GFCI circuits in kitchen with dedicated outlets for appliances
- Install 6 new 20-amp GFCI circuits in master and guest bathrooms
- Install 2 new 240V circuits for electric range and dryer
- Install 1 new 240V circuit for hot water heater
- Install new 15-amp circuit for bedroom ceiling fans
- Install new 20-amp circuit for living room entertainment center
- Install all new outlets with tamper-resistant covers
- Install new main disconnect switch with emergency shutoff
- Complete all connections per National Electrical Code (NEC)
- Perform comprehensive system testing and verification
- Obtain city inspection and approval certificate
- Provide homeowner with new electrical panel documentation

MATERIALS & EQUIPMENT

- 200-amp main breaker panel (Siemens or Square D) - $1,200
- 200-amp meter base - $350
- 200-amp main disconnect switch - $200
- GFCI outlets (20 units) - $280
- 12/2 and 10/2 copper wire (500 ft) - $420
- Circuit breakers (20 units, various amps) - $380
- Conduit, boxes, and connectors - $250
- Misc. hardware and supplies - $120

PROJECT TIMELINE

- Pre-work: Permit application and approval (3-5 business days)
- Installation Day: Panel upgrade and all circuit installation (6-8 hours)
- Inspection: City electrical inspector verification (1-2 days after completion)
- Post-Installation: 24/7 emergency electrical support available

WHY CHOOSE US

Bright Spark Electric has been Austin's premier electrical contractor for 16 years. All our electricians are Master Electricians with 15+ years experience and current certifications. We specialize in panel upgrades and have completed over 2,000 installations. We guarantee all work and offer 10-year warranty on labor.

INVESTMENT SUMMARY

Labor:	$2,200	(39%)
Materials:	$3,400	(61%)
Total:	**$5,600**	

TERMS & CONDITIONS

50% deposit ($1,900) due upon signing to secure permit application. Final 50% ($1,900) due upon completion and city inspection approval. All work includes 10-year labor warranty and 5-year parts warranty. We handle all permits and inspections. Financing available for qualifying customers.

Valid until **April 6, 2026**. Contact us to discuss or schedule your project.

✓ Professional Proposal