Arctic Breeze HVAC

(512) 847-3920 • info@arcticbreezehvac.com
2841 Ridgeline Dr, Austin, TX 78741 • Lic# HVAC-TX-88421

Complete HVAC System Replacement & Installation

CLIENT:
David & Sarah Johnson

DATE:
March 23, 2026

VALID UNTIL:
April 6, 2026

CLIENT

David & Sarah Johnson
4412 Meadowbrook Lane, Austin, TX 78745
(512) 334-7821
djohnson@email.com

JOB SITE

4412 Meadowbrook Lane, Austin TX
Single-family home, 2,400 sq ft, 2-story, 3 climate zones

PROJECT

Full HVAC System Replacement, Start: April 1, 2026, Duration: 2 days, Permit: Included

EXECUTIVE SUMMARY

Arctic Breeze HVAC is pleased to provide this proposal for a complete HVAC system replacement at your residence. Your current 15-year-old system has reached the end of its serviceable life, and we recommend replacing it with a modern, high-efficiency heat pump system that will provide superior comfort, energy savings, and reliability for years to come.

SCOPE OF WORK

- Complete removal and disposal of existing 3-ton air conditioning system and furnace
- Disconnect and cap existing refrigerant lines, drain and dispose of refrigerant per EPA regulations
- Remove existing ductwork in master bedroom zone and replace with new insulated flexible ductwork
- Install new 4-ton Carrier 25HNH448A001 high-efficiency heat pump (SEER2 16, HSPF2 9.5)
- Install new variable-speed air handler with 5-ton capacity for future expansion
- Install new smart WiFi-enabled Honeywell Home T9 thermostat with remote access capability
- Install new 1-inch return air filter with MERV-13 rating for improved air quality
- Pressure test entire system for refrigerant leaks and seal any identified leaks
- Vacuum and charge system with R-410A refrigerant to manufacturer specifications
- System startup, calibration, and full operational testing
- Provide 5-year parts warranty and 2-year labor warranty
- Complete cleanup and removal of all old equipment and packaging materials

MATERIALS & EQUIPMENT

- Carrier 25HNH448A001 Heat Pump Unit (4-ton, SEER2 16) - $2,800
- Carrier variable-speed air handler with 5-ton capacity - $1,200
- Honeywell Home T9 Smart Thermostat with WiFi - $250
- Flexible ductwork insulation (R-8) and connectors - $400
- R-410A refrigerant (20 lbs) - $180
- Electrical components and wiring - $150
- Misc. hardware, fittings, and supplies - $220

PROJECT TIMELINE

- Day 1: System removal and disposal (4-5 hours). New ductwork installation. Air handler installation.
- Day 2: Heat pump unit installation and connections. Thermostat installation. System testing and startup.
- Post-Installation: 30-day warranty period. 24/7 emergency support available.

WHY CHOOSE US

Arctic Breeze HVAC has been serving the Austin area for 18 years with a 4.9-star rating from over 500 verified customers. Our technicians are NATE-certified and factory-trained on all major brands. We offer same-day emergency service, transparent pricing with no hidden fees, and a satisfaction guarantee on all work.

INVESTMENT SUMMARY

Labor:	**$2,500**	(32%)
Materials:	**$5,200**	(68%)
Total:	**$7,700**	

TERMS & CONDITIONS

50% deposit ($3,350) due upon signing this proposal to secure your installation date. Final 50% ($3,350) due upon completion and system verification. All work includes 5-year manufacturer parts warranty and 2-year labor warranty. System includes 24/7 emergency support. Financing available through approved lenders.

Valid until **April 6, 2026**. Contact us to discuss or schedule your project.

✓ Professional Proposal