Flow Masters Plumbing

(512) 555-0123 • info@flowmastersplumbing.com
1200 Water St, Austin, TX 78704 • Lic# PLB-TX-45123

Complete Kitchen & Master Bathroom Plumbing Renovation

CLIENT:
Michael Chen

DATE:
March 23, 2026

VALID UNTIL:
April 6, 2026

CLIENT

Michael Chen
789 Oak Ridge Road, Austin, TX 78704
(512) 555-4567
mchen@email.com

JOB SITE

789 Oak Ridge Road, Austin TX
2-bedroom home built in 1995, kitchen and master bathroom complete renovation

PROJECT

Full plumbing upgrade with new fixtures, Start: April 5, 2026, Duration: 3 days, Permit: Included

EXECUTIVE SUMMARY

Flow Masters Plumbing is excited to present this comprehensive proposal for your kitchen and bathroom renovation. We will completely replace your aging plumbing infrastructure with modern copper supply lines and PVC drain lines, install premium fixtures, and ensure your home meets current plumbing codes.

SCOPE OF WORK

- Remove all existing plumbing fixtures from kitchen and master bathroom
- Cap and remove old galvanized steel supply lines throughout both areas
- Install new 3/4-inch copper supply lines from main water line to all fixtures
- Install new 1/2-inch copper branch lines to each fixture location
- Install new 2-inch and 1.5-inch PVC drain lines with proper slope and venting
- Install new P-traps and cleanouts at all drain locations
- Install new Kohler Bancroft kitchen sink with integrated drainboard
- Install new Kohler Forte kitchen faucet with pull-down sprayer
- Install new Moen Voss master bathroom vanity with dual sinks
- Install new Moen Align master bathroom faucet with motion sensor
- Install new Toto Neorest toilet with heated seat and bidet function
- Install new Delta shower valve with thermostatic mixing valve
- Install new Kohler frameless glass shower enclosure
- Complete pressure test of all supply lines (80 PSI)
- Complete smoke test of all drain lines for leaks
- Obtain city inspection and approval certificate
- Full cleanup and removal of all old materials

MATERIALS & EQUIPMENT

- Kohler Bancroft kitchen sink - $450
- Kohler Forte kitchen faucet with sprayer - $320
- Moen Voss dual-sink vanity - $680
- Moen Align bathroom faucet - $280
- Toto Neorest toilet - $1,200
- Delta shower valve and trim - $350
- Kohler frameless shower enclosure - $800
- Copper tubing and fittings (50 lbs) - $280
- PVC pipe and connectors - $150
- Valves, traps, and misc. hardware - $220

PROJECT TIMELINE

- Day 1: Demolition and removal of old fixtures and plumbing. Installation of new supply and drain lines.
- Day 2: Installation of kitchen fixtures and bathroom vanity. Toilet and shower valve installation.
- Day 3: Shower enclosure installation. Final connections and pressure testing. City inspection.
- Post-Installation: 30-day warranty period. Emergency plumber on-call.

WHY CHOOSE US

Flow Masters Plumbing has been the trusted name in Austin plumbing for 22 years. We employ only licensed, insured plumbers with an average of 12 years experience. We guarantee our work with a 2-year warranty and offer 24/7 emergency service. Our customers consistently rate us 4.8 stars for professionalism and attention to detail.

INVESTMENT SUMMARY

Labor:	**$1,800**	(26%)
Materials:	**$5,100**	(74%)
Total:	**$6,900**	

TERMS & CONDITIONS

50% deposit ($2,100) required to schedule your project and order fixtures. Final 50% ($2,100) due upon completion and inspection approval. All work includes 2-year warranty on labor and 10-year warranty on fixtures. We handle all permit applications and inspections. Financing available.

Valid until **April 6, 2026**. Contact us to discuss or schedule your project.

✓ Professional Proposal