Solid Roof Solutions

(512) 555-1111 • info@solidroof.com
777 Shingle Ave, Austin, TX 78703 • Lic# ROF-TX-56789

Complete Roof Replacement with Premium Architectural Shingles

CLIENT:
Robert Williams

DATE:
March 23, 2026

VALID UNTIL:
April 6, 2026

CLIENT

Robert Williams
555 Timber Lane, Austin, TX 78705
(512) 555-2222
rwilliams@email.com

JOB SITE

555 Timber Lane, Austin TX
1800 sq ft 2-story colonial home with 25-year-old asphalt shingles showing significant wear

PROJECT

Complete roof replacement with 30-year warranty shingles, Start: April 10, 2026, Duration: 2 days, Permit: Included

EXECUTIVE SUMMARY

Solid Roof Solutions is honored to present this proposal for your complete roof replacement. Your current roof has reached the end of its serviceable life with multiple areas of deterioration, missing shingles, and compromised flashing. We will install premium architectural shingles with a 30-year warranty, ensuring your home is protected for decades.

SCOPE OF WORK

- Obtain roofing permit from City of Austin
- Complete roof inspection and documentation of current condition
- Safely remove all existing asphalt shingles and underlying felt paper
- Inspect and replace any damaged or rotted plywood decking (estimated 150 sq ft)
- Install new 1/2-inch plywood decking where needed
- Install new synthetic underlayment for superior moisture protection
- Install new ice and water shield along all eaves and valleys
- Install new ridge vents for proper attic ventilation
- Install new GAF Timberline HD architectural shingles (30-year warranty)
- Install new aluminum flashing at all roof penetrations and valleys
- Install new gutters and downspouts (optional, quote available separately)
- Complete roof inspection and pressure wash to remove debris
- Obtain city inspection and final approval
- Provide homeowner with warranty documentation and maintenance guide
- Complete cleanup and removal of all old materials

MATERIALS & EQUIPMENT

- GAF Timberline HD architectural shingles (65 squares) - $2,100
- Synthetic underlayment and ice/water shield - $450
- Ridge vents and ventilation components - $280
- Aluminum flashing and trim - $320
- Plywood decking (150 sq ft) - $280
- Nails, fasteners, and misc. hardware - $150
- Permit and inspection fees - $100

PROJECT TIMELINE

- Pre-work: Permit application (3-5 business days)
- Day 1: Complete removal of old roofing and inspection. Installation of new decking and underlayment.
- Day 2: Installation of ice/water shield, shingles, flashing, and ridge vents. Final inspection.
- Post-Installation: 30-year manufacturer warranty. 5-year labor warranty. Emergency repair hotline.

WHY CHOOSE US

Solid Roof Solutions has been Austin's trusted roofing company for 20 years. We are GAF Master Elite contractors, the highest certification available. Our team has completed over 5,000 roof replacements with a 4.9-star customer rating. We stand behind our work with a 5-year labor warranty and handle all permits and inspections.

INVESTMENT SUMMARY

Labor:	$3,500	(49%)
Materials:	$3,680	(51%)
Total:	**$7,180**	

TERMS & CONDITIONS

50% deposit ($3,150) required to schedule your project and order materials. Final 50% ($3,150) due upon completion and city inspection approval. All work includes 30-year manufacturer warranty on shingles and 5-year labor warranty. We handle all permits. Financing available for qualified customers.

Valid until **April 6, 2026**. Contact us to discuss or schedule your project.

✓ Professional Proposal