Arctic Breeze HVAC

Licensed & Insured Contractor · Lic# HVAC-TX-88421

HVAC System Replacement & Installation

Prepared for David & Sarah Johnson · March 23, 2026

CLIENT

David & Sarah Johnson
4412 Meadowbrook Lane, Austin, TX 78745
(512) 334-7821
djohnson@email.com

JOB SITE

4412 Meadowbrook Lane, Austin, TX 78745 — Single-family home, 2,400 sq ft, 2-story, 3 zones

PREPARED BY

Arctic Breeze HVAC
(512) 847-3920
info@arcticbreezehvac.com

PROPOSAL VALID UNTIL

April 6, 2026

TOTAL INVESTMENT	SCOPE ITEMS	TIMELINE
$7,697.00	8 Services	4 Phases

PROJECT OVERVIEW

This proposal outlines the comprehensive replacement of your existing 3-ton HVAC system at 4412 Meadowbrook Lane with a new, high-efficiency Carrier 16 SEER system. Our solution ensures improved comfort, energy savings, and reliable performance for your property, backed by our commitment to quality workmanship and 25 years of industry experience.

WHAT'S INCLUDED

- ✓ System Disconnection & Removal
- ✓ New Indoor Coil Installation
- ✓ Thermostat Upgrade
- ✓ Warranty & guarantee
- ✓ New Outdoor Unit Installation
- ✓ Refrigerant Line Replacement
- ✓ All materials & equipment
- ✓ Site cleanup & walkthrough

OUR COMMITMENT TO YOU

Licensed & Insured

5-Star Rated

Satisfaction Guaranteed

Warranty Included

1 Scope of Work

#	DESCRIPTION
1	System Disconnection & Removal: Safely disconnect and remove the existing 3-ton outdoor air conditioning unit and indoor coil/furnace. All old refrigerant will be recovered and disposed of environmentally responsibly.
2	New Outdoor Unit Installation: Install a new Carrier 24ACC336A003 3-ton 16 SEER air conditioning condenser unit on an approved equipment pad in the existing location.
3	New Indoor Coil Installation: Install a new Carrier evaporator coil, properly matched to the new outdoor unit, within your existing furnace or air handler plenum.
4	Refrigerant Line Replacement: Install new, appropriately sized copper refrigerant lines between the new outdoor condenser unit and the new indoor evaporator coil with all necessary insulation and fittings.
5	Thermostat Upgrade: Install a new Honeywell Home T6 Pro programmable thermostat for precise temperature control and energy management.
6	Ductwork Inspection & Sealing: Inspect all accessible ductwork for leaks, damage, or disconnections. Seal any identified leaks with mastic sealant to improve system efficiency.
7	Electrical Connections: Make all necessary electrical connections for the new outdoor and indoor units, ensuring compliance with local electrical codes.
8	System Startup & Testing: Perform complete system startup, charge verification, airflow testing across all zones, and operational check of all components.

2 Materials & Equipment

	ITEM
•	Carrier 24ACC336A003 — 3-Ton 16 SEER AC Condenser Unit
•	Carrier CNPVP3617ALA — Cased Evaporator Coil
•	Honeywell Home T6 Pro Programmable Thermostat
•	3/8" & 3/4" Insulated Copper Refrigerant Line Set (up to 50 ft)
•	R-410A Refrigerant (factory charge + field adjustment)
•	Condensate Drain Line & Safety Float Switch
•	Equipment Mounting Pad & Vibration Isolators
•	Mastic Duct Sealant & Foil Tape for Ductwork Repairs

3 Project Timeline

- Day 1 (Morning): Equipment delivery, site preparation, and removal of existing outdoor condenser and indoor coil.
- Day 1 (Afternoon): Installation of new outdoor condenser unit, new refrigerant lines, and electrical connections.
- Day 2 (Morning): Installation of new indoor evaporator coil, thermostat, and condensate drain.
- Day 2 (Afternoon): System startup, refrigerant charge verification, airflow testing, zone balancing, and final walkthrough with homeowner.

★ Why Choose Us

Arctic Breeze HVAC has served the Austin area for over 25 years. We are fully licensed, bonded, and insured. Our technicians are NATE-certified and factory-trained on all major brands. We offer a 10-year parts warranty and a 2-year labor warranty on all installations. Our A+ BBB rating and 4.9-star Google reviews reflect our commitment to customer satisfaction.

IMPORTANT INFORMATION

This proposal includes all labor, materials, and equipment necessary to complete the project as described above. Our commitment to quality ensures:

- Licensed & insured work
- Manufacturer warranties
- Post-project inspection
- Code-compliant installation
- Complete site cleanup
- Satisfaction guarantee

4 Investment Summary

LABOR

$2,450.00

MATERIALS

$5,247.00

TOTAL PROJECT INVESTMENT

$7,697.00

Cost Breakdown



5 Payment Schedule

DEPOSIT (50%)	BALANCE (50%)
$3,848.50	**$3,848.50**
Due upon acceptance	Due upon completion

✓ **WARRANTY & GUARANTEE**

All work is guaranteed to meet or exceed local building codes and manufacturer specifications. We stand behind our workmanship and materials with comprehensive warranty coverage for your peace of mind.

6 Terms & Conditions

A 50% deposit ($3,848.50) is required upon acceptance of this proposal. The remaining balance is due upon satisfactory completion of the installation. This proposal is valid for 14 days from the date above. Any changes to the scope of work may result in additional charges, which will be communicated and approved in writing before proceeding. All work is guaranteed to meet or exceed local building codes and manufacturer specifications.

Thank You for Considering Arctic Breeze HVAC

We look forward to working with you. Please don't hesitate to reach out with any questions.

CLIENT SIGNATURE

Date: _____

CONTRACTOR SIGNATURE

Date: _____